

## **SEPARATION DISTANCES FROM INGROUND PROPANE TANKS TO SEWAGE DISPOSAL SYSTEMS AND ONSITE WELLS**

- **PROPANE TANK TO SEPTIC TANK – 10 FEET**
- **PROPANE TANK TO DOWNGRAIDENT LEACHING SYSTEM – 15 FEET**
- **PROPANE TANK TO UPGRADIENT LEACHING SYSTEM – 25 FEET.**
- **EXCESSIVELY LARGE (>15 FT) PROPANE TANK TO UPGRADIENT LEACHING SYSTEM – 50 FEET**
- **BURIED PIPING TO ANY PART OF SEWAGE DISPOSAL SYSTEM – 5 FEET**
- **PROPANE TANK TO ONSITE WELL – 25 FEET**